GOVERNMENT OF ANDHRA PRADESH

ABSTRACT

Water Resources Department – IOCL – Laying of 4" dia underground Steel Pipeline, Optical Fiber Cable (OFC) along with 125 mm Medium Density Poly Ethylene (MDPE) for Public Utility City Gas Distribution (CGD) crossing Guntur Channel @ KM 4.300 Kolanukonda besides NH -16 of Vaddeswaram (V), Tadepalli (M) in Guntur District by Indian Oil Corporation Limited - Permission Accorded –Orders – Issued.

WATER RESOURCES (REFORMS) DEPARTMENT

G.O.Rt.No.272 **Dated:12.08.2024**

Read the following:

1.IOCL letter No. SERPL/CGD/GNT/WRD/23/03, Dt. 10-11-2023 addressed to SE/IC/GNT.

2.G.O.Ms.No 1,Water Resources (Reforms)Dept., Dt 03-01-2024.

3.Chief Engineer, KDS, Vijayawada, Lr. No. CE/KDS/VJA/OT-2/AEE-5/GC/350, Dt. 05-03-2024.

4.From the Engineer-in-Chief (Irrigation), WRD, Lr.No: ENC(I)/EE/DEE1/ AEE2/IWS/IOCL, Dt.14 -03-2024.

****

O R D E R:

In the letter 4th read above, the Engineer-in-Chief (Irrigation), Water Resources Department, Vijayawada has recommended the proposal for according permission to the Indian Oil Corporation Ltd. (IOCL) for laying of 4" dia underground Steel Pipeline, Optical Fiber Cable (OFC) along with 125 mm Medium Density Poly Ethylene (MDPE) for Public Utility City Gas Distribution (CGD) crossing Guntur Channel @ KM 4.300 Kolanukonda besides NH -16 of Vaddeswaram (V), Tadepalli (M) in Guntur District. The Engineer- in-Chief (Irrigation) has also furnished the following details of the lease amounts and Security Deposits (BG-Refundable) to be paid by the IOCL :

Name of the Division	Lease amount for 10 years (Non-Refundable)	Security Deposits (BG- Refundable)
Irrigation Division, Guntur	Rs.2,43,000/- (Calculation Sheet Enclosed) (page 10 cf)	Rs. 3,41,000/- (Estimate Copy Enclosed)

2. Under the circumstances explained in the letter 4th read above, the Engineer-in-Chief (Irrigation), Water Resources Department, Vijayawada has requested the Government to accord necessary permission to the Indian Oil Corporation Limited for laying of 4" dia underground Steel Pipeline, Optical Fiber Cable (OFC) along with 125 mm Medium Density Poly Ethylene (MDPE) for Public Utility City Gas Distribution (CGD) crossing Guntur Channel @ KM 4.300 Kolanukonda besides NH -16 of Vaddeswaram (V), Tadepalli (M) in Guntur District for lease amounts mentioned at above para and subject to the following terms and conditions to be implemented for laying Pipeline:

1.The IOCL authorities have to pay security deposit (BG-Refundable) for an amount of Rs 3,41,000/-(Rupees Three lakhs Forty One thousand only)

in favour of the Executive Engineer, Irrigation Division, Guntur before commencement of the work.

2.The firm has to pay the lease amount of Rs 2,43,600/-(Rupees Two lakhs Forty Three thousand only) for the above said crossing for 10 years (Non-Refundable) in advance to the Government in favour of the Executive Engineer, Irrigation Division, Guntur as long as the agreement of lease is in force.

3.The IOCL authorities shall hand over the Demand Draft / Bank Guarantee to the Executive Engineer, Irrigation Division, Guntur and get permission to execute the work well in advance.

4.The Water Resources Department reserves the right to denial of crossing of the pipeline of the IOCL, if it is found to be causing any sort of damage to the structural stability and hindrance to flow of water in the Guntur Channel.

5.The IOCL authorities should execute the pipeline crossing work without altering the existing hydraulic particulars and natural profile of the Guntur Channel.

6.After execution of the work, the IOCL authorities should restore the Guntur Channel to the original standards as directed by the Engineer- in-Charge of the Water Resources Department.

7.The Water Resources Department reserves the right of modification/ alteration / up gradation of the department's property without the consent of IOCL and the company authorities should oblige the same without any changes.

8.The pipeline shall be laid duly maintaining minimum of 4.00 M clear cushion from the ground or below designate Bed Level of the Guntur Channel at crossing point.

9.The pipeline should be laid preferably by Horizontal Direction Drilling (HDD) method for bed width more than 7.00 m without disturbing the existing embankments.

10.For laying of the above pipeline open excavation should not be permitted on the Guntur Channel. If any unavoidable situation arises during laying of the pipeline, necessary diversion arrangements are to be made for free flow of water in the Guntur Channel.

11.During laying of the pipeline if the canal is disturbed, the firm is liable for restoration of canal to its original standards with their own cost and as directed by the Engineer-in-Charge of the Water Resources Department.

12.If any damage is caused to crop or habitations in the vicinity, the sole responsibility shall lie with the applicant firm and adequate compensation should be paid by the from to the farmers or people affected with the damage.

13.After laying the pipeline, the canal should be restored to its original standards and No objection Certificates (NOC) may be obtained from the concerned officials of the Water Resources Department to get release of the security deposit.

14.Safety of the pipeline laid is the sole responsibility of the IOCL.

15.After execution of laying of the pipeline, proper compaction is to be done and bank is to be restored to designated profile.

16.Any other conditions if found necessary by the Water Resources Department/ Government after according permission, the same should be abide by the IOCL.

17.While execution of the work, proper care is to be taken for protecting the salient features of the Guntur Channel. In case of any damage caused to Irrigation system, the same should be restored immediately by reconstruction of the same at the cost of the IOCL to the required standards.

18.There shall not be any obstruction for the free flow of the water/ Navigation during the execution of the work or after the completion of the work.

19.The firm has to intimate 15 days before the commencement of work and the work has to be done under the close supervision of Water Resources Department staff only.
20.The permission accorded shall be liable to cancel at any time, when the situation demands any objections raised from the ayacutdars without any prior notice and the IOCL have no right to claim any compensation in this regard.
21.While doing excavation of trenches with earth moving machinery, the soil is to be dumped away from the Guntur Channel bed.
22.Similarly refilling of trench after erection of pipeline and OFC cable laying shall be carried out without obstructing the flow in the Guntur Channel.
23.The run-off yield through Nalas and Drains at crossing point of Guntur Channel should neither be diverted nor percolated into pipeline trenches.
24.The excavation of trenches must be well beneath the bed of Nala or Drain at crossing point of Guntur Channel.
25.The pipeline alignment should not block the discharge of flow in the Nala or Drain at the crossing point of the Guntur Channel. If any blockage of the Nala or Drain during laying of the above pipeline, the IOCL should be cleared the blockage for free flow of Nala or Drain.
26.The applicant has to construct the required structures with his own expenditure and not to claim rights either on the structure or on the extent of course and area occupied by the structures. The approach crossing is under the control of Water Resources Department, Government of A.P. only.
27.Any damage caused to the Government properties should be rectified by the IOCL authorities at their own cost.
28.The IOCL authorities should not make any alterations of the proposals without the consent of the Water Resources Department.
29.The Water Resources Department is no way responsible for any legal complications arising by the public or other on the above pipeline work operation of the firm.
30.If any modification is required for the pipeline in future due to development activity in the Guntur Channel, the IOCL shall carry out the modification for the pipeline at their own cost to the satisfaction of the Water Resources Department.

3. Government after careful examination of the matter, hereby accord permission to the Indian Oil Corporation Limited (IOCL) for laying of 4" dia underground Steel Pipeline, Optical Fiber Cable (OFC) along with 125 mm Medium Density Poly Ethylene (MDPE) for Public Utility City Gas Distribution (CGD) crossing Guntur Channel @ KM 4.300 Kolanukonda besides NH -16 of Vaddeswaram (V), Tadepalli (M) in Guntur District for the proposed pipeline crossings with the calculations for lease amounts as mentioned at para-(1) above and subject to the terms and conditions as mentioned at para-(2) above.

4. The Engineer-in-Chief (Irrigation), Water Resources Department, Andhra Pradesh, Vijayawada and the Collector & District Magistrate of Guntur District and the Chief Engineer, Krishna Delta System, Vijayawada shall take necessary action accordingly.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

G SAI PRASAD
SPECIAL CHIEF SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief (Irrigation), Water Resources Department,
Andhra Pradesh, Vijayawada.

The Collector & District Magistrate, Guntur, District.
The Chief Engineer Krishna Delta System, Vijayawada
The Manager, Indian Oil Corporation Limited, City Gas Distribution,
D.No.3-14-59, 1st Floor, 1st Lane, Pattabhipuram, Guntur-522006.
The District Authority, District Pollution Control Board, Guntur District.
Copy to:
The P.S. to Honsble Minister for Water Resources.
The P.S. to the Spl. C.S. to Government, Water Resources Dept.
The Superintending Engineer, Irrigation Circle, Guntur.
SF/SC.

//FORWARDED::BY ORDER//

SECTION OFFICER